

COC Pre-Inspection Checklist



Use this checklist before the electrician arrives to avoid obvious failures and speed up the process:

Before the electrician arrives, check:

- All plug points have covers (no missing faceplates)
- No loose hanging wires anywhere in the home
- Geyser isolator is *reachable and clearly visible*
- DB board is accessible (*not blocked by furniture or boxes*)
- Outside lights are properly sealed (*no exposed wiring*)
- Pool pump wiring is protected in conduit
- No open junction boxes in roof or ceiling
- All circuit breakers in the DB board are labeled
- Earth leakage test button is functioning
- No cracked or damaged plugs or switches visible

Note: This checklist is for preparation purposes only and does not replace a formal inspection.
For any uncertainties, leave it for the professional electrician.

Book Your COC Inspection Today!

Ensure your home is compliant and safe!



This guide was provided by the Fonster team - fonster.co.za

 **ONSTER**